HASSAN DIVISION.

ADVERTISEMENT.

The 27th March 1892.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 27th April 1892, for re-constructing 2 blocks of Barr Lines at Hassan. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1893.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan between the hours of 11 A. M. and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for reconstructing 2 blocks of Barr Lines at Hassan"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

For each Block.

Items of Work.	Per.	Rate.	Quantity.
Excavating foundation	C. Yd.		234
Burnt brick in clay	C. Ft.		24,214
Do brick in chunam	do		1,928
Plastering with mortar	Sq.		140·27
Do with mud	do		187·76
Flooring with gravel	C. Yd.		64
Burnt stone slabs dressed	Sq. Ft.		562
Jungle wood work wrought and put up complete	C. Ft.		298 33
Roofing with Mangalore flat tiles and teak reepers 2″ × 1″ ..	Sq.		65·60
Ridging with Mangalore ridge tiles	R. Ft.		164
Mangalore ventilating tiles	Each.		44
White washing 2 coats	Sq.		299·57
Jungle wood doors with battened shutters and frames, &c., 3 × 6 ..	Each.		44
Do do in compound wall 2½′ × 5′	do		22
Ventilators or windows 2½′ × 1½′	do		44
Coping with chunam	R. Ft.		1,001
V shaped drain backed with concrete	do		324
Dismantling present line	C. Ft.		20·153

A. S. NAGAVKAR,
Executive Engineer.

Abstract of Meteorological Register kept at the undermentioned District Head-Quarters for the fortnight ending 15th March 1892.

Head-Quarters.	Thermometer. *Averages for the half month.* 9-30 A. M. Dry bulb.	9-30 A. M. Wet bulb.	9-30 A. M. Difference.	3-30 P. M. Dry bulb.	3-30 P. M. Wet bulb.	3-30 P. M. Difference.	Thermometer. Maximum.	Thermometer. Minimum.	Rain. Inches.	Rain. Cents.	Wind.
Hassan ...	79	63	16	89	65	24	90	65	...	5	
Chitaldroog ...	83	69	14	88	70	18	93	70	...	...	
Kolar ...	...	...	...	...	...	...	...	...	...	...	
Chikmagalur* ...	...	...	...	...	...	...	...	...	...	...	
Shimoga* ...	...	...	...	...	...	...	...	...	...	...	
Tumkur* ...	...	...	...	...	...	...	...	...	...	...	
Mysore * ...	...	...	...	...	...	...	...	...	...	...	

* Information not received from other stations.